



**Skilled
Trades**
Ontario

**Métiers
spécialisés**
Ontario

Apprenticeship
Curriculum Standard

Terrazzo, Tile and
Marble Setter

Level 2

241A

2009

Apprenticeship Pathway to a Certificate of Qualification

Phase 1: Registration

Submit Application for Apprenticeship Training through the on-line portal or to local Service Delivery Office

For on-line portal, please follow instructions for registration. You will need to create a *My Ontario* account to access online services.

Training agreement signed and registered by both apprentice and sponsor

Access your Apprenticeship Training Standard Logbook**
skilledtradesontario.ca/about-trades/trades-information

** This is the official record of your training progress. You are responsible for keeping it up-to-date.

Complete on-the-job training

Demonstrate and receive sign-off on the competencies/skills in your Apprenticeship Training Standard Logbook

Complete in-school training

Attend and complete the in-class training set out in the Curriculum Training Standard

Apprentices eligible to apply for apprenticeship incentive grants (Red Seal trades) and loans.

Review and finalize your logbook with your sponsor

Submit proof of apprenticeship completion via email, in-person or digital portal

Your Apprenticeship Training Standard Logbook details completion requirements. Submit the following:

- completed Apprenticeship Training Standard Logbook with signatures
- proof of hours

Certificate of Apprenticeship is issued

Trades without examination

CofA is the final step of the program

Trades with examination (compulsory and non-compulsory trades)*

Provisional Certificate of Qualification issued for a 12 month term

To prepare for the CofQ examination download the Provincial and/or Red Seal Exam preparation guides.

Make payment for your Certificate of Qualification examination

Call to make a payment (647-847-3000 or 1-855-299-0028)

Schedule a date to write your Examination

To schedule your examination, contact your local Service Delivery Office.

Pass Certificate of Qualification examination

Apprentices eligible to apply for Apprenticeship Completion Grant (Red Seal trades) or Apprentice Completion Bonus (non-Red Seal)

Certificate of Qualification is issued

Upon completion, Sponsors may be eligible for Apprenticeship grants, incentives, bonuses or tax credits

Phase 2: Apprenticeship

Phase 3: Certification

* For a list of trades subject to a certification examination, visit: skilledtradesontario.ca

Table of Contents

Preface.....	1
Introduction	2
Level 2.....	3
Reportable Subject Summary-Level 2.....	4
S1139 Trade Practices And Procedures II	5
S1139.1 Material Specifications	6
S1139.2 Restoring Existing Surfaces	9
S1139.3 Finalize Projects	11
S1139.4 Job Site Conditions	12
S1140 Reading And Construction Geometry II	14
S1140.1 Material Specifications	15
S1140.2 Blueprint Notices, Addenda And Revisions	16
S1140.3 Construction Geometry	17
S1140.4 Material Layout Plan	18
S1140.5 Interpret Construction Drawings	19
S1141 Construction Techniques And Procedures II	20
S1141.1 Construction Techniques Planning And Preparation	21
S1141.2 Substrate Preparation	23
S1142 Terrazzo Installation II	27
S1142.1 Install Terrazzo Base	28
S1142.2 Install Specialty Terrazzo	32
S1142.3 Install Terrazzo On Stairs, Bases And Walls	34
S1143 Tile Installation II	36
S1143.1 Tile Pattern Design	37
S1143.2 Tile Layout	39
S1143.3 Tile Installation	40
S1144 Natural Stone Installation II	43
S1144.1 Mechanical Installation	44
S1144.2 Interior Conventional And Stacking Installation	47

Terrazzo, Tile and Marble Setter

S1144.3	Material Specifications	50
S1144.4	Counter Top Installation	52
APPENDIX I	55
Suggested Projects Level II:	58

Please Note: This Standard has been revised to reflect the visual identity of Skilled Trades Ontario (STO) which replaced the Ontario College of Trades on January 1, 2022. The content of this Standard may refer to the former organization; however, all trade specific information or content remains relevant and accurate based on the original date of publishing.

Please refer to STO's website: skilledtradesontario.ca for the most accurate and up to date information. For information about BOSTA and its regulations, please visit [Building Opportunities in the Skilled Trades Act, 2021 \(BOSTA\)](#).

Any updates to this publication are available on-line; to download this document in PDF format, please follow the link: Skilled Trades Ontario.ca.

© 2022, Skilled Trades Ontario. All rights reserved. No part of this publication may be reproduced in any form whatsoever without the prior permission from Skilled Trades Ontario.

Maintained with transfer to Skilled Trades Ontario 2009 (V100)

Preface

This curriculum standard for the Terrazzo, Tile and Marble Setter program is based upon the on-the-job performance objectives, located in the industry-approved training standard.

The curriculum is organized into 2 levels of training. The Reportable Subjects Summary chart (located on page 4) summarizes the training hours for each reportable subject.

The curriculum identifies the learning that takes place in-school. The in-school program focuses primarily on the theoretical knowledge and the essential skills required to support the performance objectives of the Apprenticeship Training Standards.

Employers/Sponsors are expected to extend the apprentice's knowledge and skills through practical training on a work site. Regular evaluations of the apprentice's knowledge and skills are conducted throughout training to verify that all apprentices have achieved the learning outcomes identified in the curriculum standard.

It is not the intent of the in-school curriculum to perfect on-the-job skills. The practical portion of the in-school program is used to reinforce theoretical knowledge. Skill training is provided on the job.

Please refer to Skilled Trades Ontario website (www.skilledtradesontario.ca) for the most accurate and up-to-date information about Skilled Trades Ontario. For information on *Building Opportunities in the Skilled Trades Act, 2021 (BOSTA)* and its regulations, please visit [Building Opportunities in the Skilled Trades Act, 2021, S.O. 2021, c. 28 - Bill 288 \(ontario.ca\)](http://www.skilledtradesontario.ca/building-opportunities-in-the-skilled-trades-act-2021-s.o.-2021-c.-28-bill-288)

Pre-requisites

In order to advance to Level 2 of the apprenticeship program, an individual must have completed all of the units outlined in Level 1.

Hours Disclaimer (if applicable)

It is agreed that Training Delivery Agents (TDAs) may need to make slight adjustments (with cause) according to particular apprentice needs and may deviate from the unit sequencing and the prescribed practical and theoretical hours shown within the standard. However, all TDAs will comply with the hours at the reportable subject level.

Suggested Equipment for Training Delivery Agencies

The listing of tools on page 53 to 56 does not list minimum quantities based on the understanding that the delivering TDA is in the best position to determine the need based on its delivery methodology.

Personal and Safety Equipment: Personal protective equipment is at the discretion of the TDA who must conform to Ontario Provincial Health and Safety Regulations

Introduction

This new curriculum standard for the Terrazzo, Tile and Marble Setter trade or modular program is based upon the on-the-job performance objectives, located in the industry-approved training standard.

The curriculum is organized into 2 levels of training or 6 reportable subjects per Level. The Program Summary of Reportable Subjects chart summarizes the training hours for each reportable subject.

The curriculum identifies only the learning that takes place off-the-job. The in-school program focuses primarily on the theoretical knowledge and the essential skills required to support the performance objectives of the Apprenticeship or Modular Training Standards. Employers/Sponsors are expected to extend the apprentices or trainee's knowledge and skills through practical training on the work site. Regular evaluations of the apprentice's or trainee's knowledge and skills are conducted throughout training to ensure that all apprentices or trainees have achieved the learning outcomes identified in the curriculum standard.

It is not the intent of the in-school curriculum to perfect on-the-job skills. The practical portion of the in-school program is used to reinforce theoretical knowledge. Skill training is provided on the job

Level 2

Reportable Subject Summary-Level 2

Number	Reportable Subjects	Hours Total	Hours Theory	Hours Practical
S1139	Trade Practices and Procedures II	60	30	30
S1140	Blueprint Reading and Construction Geometry II	45	25	20
S1141	Construction Techniques & Procedures II	60	10	50
S1142	Terrazzo Installation II	60	15	45
S1143	Tile Installation II	60	17	43
S1144	Natural Stone Installation II	75	15	60
	Total	360	112	248

Number:	S1139		
Title:	Trade Practices And Procedures II		
Duration:	Total Hours: 60	Theory: 30	Practical: 30
Prerequisites:	None		
Content:	S1139.1 Material Specifications S1139.2 Restoring Existing Surfaces S1139.3 Finalize Projects S1139.4 Job Site Conditions		

Evaluation & Testing: - Assignments related to theory and appropriate application skills

- Minimum of one mid-term test during the term
- Final exam at end of term
- Periodic quizzes

Instructional and Delivery Strategies:

- Lecture and assignment work.

Reference Materials:

Product information as supplied by the manufacturer:

- General installation procedures
- Tool adjustments
- Warranty requirements
- Required installation material
- Conditions for installation

Number: S1139.1
Title: **Material Specifications**
Duration: Total Hours: 12 Theory: 12 Practical: 0
Cross Reference to Training Standard: U0854.02, U0855.01 to U0855.03, U0856.01

General Learning Outcomes

Describe material specifications including characteristics and bonding material applications in accordance with manufacturers and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1139.1.1 Describe the following material characteristics:

- Mortars
 - Dry-set mortar - Portland cement, Sand & water retentive additives
 - Latex-Portland cement mortars - a two component liquid latex mixed with factory blended dry-set mortar
 - Light weight mortar - polymer-modified non-sag mortar
 - Full contact mortars – High performance, polymer modified mortars
 - Fast setting mortars – Epoxy mortars/ epoxy resin and hardener used for high bond strength and chemical resistance
 - Furan resin mortar consisting of carbon and/or silica filled furan resin and hardener
- Bond strength
 - Mortar bed
 - Setting material
 - Terrazzo topping
 - Tile
- Hardness
 - Extra heavy commercial
 - Heavy commercial
 - Moderate normal commercial
 - Light commercial
 - Residential

- Absorption
 - Percent of moisture penetration by weight for marble, granite, limestone, slate, tile and engineered stone

- Compressive shear strength for force applied to:
 - Glazed wall tile
 - Mosaic tile
 - Quarry tile
 - Porcelain tile
 - Marble
 - Granite
 - Limestone
 - Slate
 - Engineered stone

- Abrasiveness
 - Light traffic abrasive hardness (HA) 6 minimum
 - Moderate traffic abrasive hardness (HA) 7 to 10
 - Heavy traffic abrasive hardness (HA) 12 minimum

- Porosity
 - Percent of water by weight absorbed
 - Setting material
 - Exterior and interior installations

- Contraction and expansion factors
 - Thermal expansion
 - Temperature changes
 - Interior
 - Interior/sunlight
 - Exterior – normal
 - Exterior – excessive
 - Cold – joint
 - Isolation – joint
 - Structural - joint

S1139.1.2 Describe the properties and applications of bonding materials used on terrazzo, tile and natural stone.

- Dry-Set mortars
 - Epoxy based
 - Latex based
 - Portland cement

- Glues
 - Water based
 - Solvent based

- Mortars
 - Sand
 - Cement
 - Latex

S1139.1.3 Explain the construction features of mechanical systems and their applications.

- Fasteners (angles, bolts, wedges, hooks and pins)
- Anchoring systems
- Strut systems
- Spring nuts
- Shims and spacers
- Clips
- Accessories

S1139.1.4 Explain the reason for the specific applications of admixtures.

- Colouring agents for:
 - portland cement terrazzo
 - epoxy terrazzo
 - grout

- Curing agents and sealers
 - water – based
 - solvent – based

- Retardants for setting-up process or aggregate

- Accelerators for fast - setting

S1139.1.5 Describe the handling and disposal process for chemicals as prescribed by the Workplace Hazardous Materials Information System (WHMIS) under the Occupational Health and Safety Act.

- Location
- Containers
- Ventilation

Number: S1139.2
Title: **Restoring Existing Surfaces**
Duration: Total Hours: 25 Theory: 5 Practical: 20
Cross Reference to Training Standard U0856.13, U0859.02, U0861.11, U0862.09

General Learning Outcomes

Restore existing surfaces in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1139.2.1 Describe the steps required to restore existing surfaces.
- Remove existing materials
 - Clean and sweep preparation area
 - Remove any foreign substance
 - Install new underlayment to conform to surrounding area.
 - Mortar bed
 - Crack isolation membranes
 - Waterproof membranes
 - Levelling coat
- S1139.2.2 Review the potential hazards associated with the restoration of existing surfaces.
- S1139.2.3 Review the requirements for Workers' Compensation Coverage, WHMIS training and Material Safety Data Sheets, Emergency First-Aid, Fire Procedures and Safety committees.
- S1139.2.4 Perform specified procedures to prepare surfaces to be restored.
- Effective cleaning methods
 - Remove contaminants such as oil, sealers & curing compounds
 - Sweep clean
 - Vacuum
 - Wash
 - Shot blasting
 - Sand blasting
 - Grinding
 - Scarifying

Terrazzo, Tile and Marble Setter

- S1139.2.5 Perform restoration work with new materials.
- Matching types
 - Matching colours
 - Matching finish
 - Textured to finished floor
- S1139.2.6 Perform steps required to perform a successful job cleanup and repair of existing surfaces.
- S1139.2.7 Finish restored surfaces to specified condition appropriate for the surrounding area

Number: S1139.3
Title: **Finalize Projects**
Duration: Total Hours: 15 Theory: 5 Practical: 10
Cross Reference to Training Standard: U0851.01, U0857.06, U0858.14, U0860.06

General Learning Outcomes

Finalize work projects in accordance with manufacturer's recommendations and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1139.3.1 Describe the importance and details of check-off procedures for finishing projects.
- S1139.3.2 Explain the purpose and contents of deficiency lists.
- S1139.3.3 Apply the steps required for final cleaning of various types of terrazzo, tile and natural stone surfaces.
- S1139.3.4 Remove and store tools and equipment from the work site to the assigned storage area.

Number:	S1139.4		
Title:	Job Site Conditions		
Duration:	Total Hours: 8	Theory: 8	Practical: 0
Cross Reference to Training Standard: U0854.01 to U0854.07			

General Learning Outcomes

Describe the job site conditions required to produce quality work in accordance with government safety regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1139.4.1 Identify the job site conditions required for effective installations.
- Conformance to job specifications
 - Check off list
 - Parameters of measuring equipment
 - Obstructions
 - Available power and utilities
 - Accessibility for people and equipment
- S1139.4.2 Outline the factors required to verify the accuracy of drawings.
- Accuracy of materials list
 - Material type
 - Material quantity
 - Material quality
- S1139.4.3 Identify the common causes of work stoppage.
- Excess moisture
 - Unstable substrate
 - Lack of security
 - Insufficient lighting
 - Inadequate ventilation
 - Lack of electrical power
 - Inaccurate temperature for curing requirements
- S1139.4.4 Describe the job site material handling practices.
- Motorized and non-motorized vehicles
 - Dollies
 - Rigging equipment (chain block)
 - Securing materials
 - Lifting techniques

- Safe lifting weights

S1139.4.5 Outline the recommended material storing techniques.

- Protection of materials from elements.
 - Covering
 - Sheltering
 - Insulating
 - Heating

S1139.4.6 Describe the application of personal lifting devices and equipment.

- Scissor lifts (cherry picker)
- Hydraulic lifts/platform lifts
- Ladders
- Basic scaffolds
- Swing stages
- Zoom boom

S1139.4.7 Outline the recommended disposal practices for job site materials.

- Recycling practices
- Removing practices
- Disposing of hazardous and non-hazardous materials
- Extra materials for future repairs

Evaluation Structure				
Theory Testing	Practical Application Testing	Projects	Notebook & organizational Skills	Final Assessment
10%	60%	10%	5%	15%

Number:	S1140		
Title:	Blueprint Reading And Construction Geometry II		
Duration:	Total Hours: 45	Theory: 25	Practical: 20
Prerequisites:	None		
Content:	S1140.1Blueprint Views and Sections S1140.2Blueprint Notices, Addenda and Revisions S1140.3Construction Geometry S1140.4Material Layout Plan S1140.5Interpret Construction Drawings		

- Evaluation & Testing:
- Assignments related to theory and appropriate application skills
 - Minimum of one mid-term test during the term
 - Final exam at end of term
 - Periodic quizzes

Instructional and Delivery Strategies:

- Lecture and assignment work.

Product information as supplied by the manufacturer:

- General installation procedures
- Tool adjustments
- Warranty requirements
- Required installation material
- Conditions for installation

Number:	S1140.1		
Title:	Blueprint Views and Sections		
Duration:	Total Hours: 14	Theory: 8	Practical: 6
Cross Reference to Training Standard: U0854.02, U0855.01			

General Learning Outcomes

Identify the views and sections used on project installation blueprints in accordance with manufacturers' specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1140.1.1 Describe the details of the views and sections used on blueprints.
- Front view
 - Side view
 - Plan (top) view
 - Sections
 - Details and schedules
 - Abbreviations and title blocks on orthographic drawings
- S1140.1.2 Explain how notices, addenda and revisions are indicated and issued.
- S1140.1.3 Apply generally accepted principles in layout.
- Reference to the site conditions
 - Starting point
 - Bench marks
 - Use of tools
 - water levels/squares/measuring tapes/ chalk lines/ plumb bobs/laser levels and transits, hand levels, straight edges and mason lines.

Number: S1140.2
Title: **Blueprint Notices, Addenda And Revisions**
Duration: Total Hours: 6 Theory: 6 Practical: 0
Cross Reference to Training Standard U0854.02, U0855.01

General Learning Outcomes

Explain how notices, addenda and revisions are presented on project installation blueprints in accordance with manufacturers' specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1140.2.1 Define examples of notices, addenda and revisions for installation blueprints.
- Notices
 - warning of changes
 - Addenda
 - additional extra work or deletion
 - Revisions
 - changes from original drawing
- S1140.2.2 Explain how notices, addenda and revisions are indicated and issued for installation blueprints.

Number: S1140.3
Title: **Construction Geometry**
Duration: Total Hours: 8 Theory: 3 Practical: 5
Cross Reference to Training Standard: U0854.02, U0855.01

General Learning Outcomes

Perform operations in construction geometry in accordance with manufacturers' specifications.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1140.3.1 Draw parallel lines.
- S1140.3.2 Bisect lines and angles.
- S1140.3.3 Determine the radius of:
 - An arc
 - Centre of a circle
 - Laying out a regular polygon
- S1140.3.4 Perform operations in construction geometry for a typical site drawing.
 - Terrazzo installation
 - Tile installation
 - Natural Stone installation

Number: S1140.4
Title: **Material Layout Plan**
Duration: Total Hours: 14 Theory: 5 Practical: 9
Cross Reference to Training Standard: U0854.01 to U0854.03

General Learning Outcomes

Perform layout procedures for assigned terrazzo, tile and natural stone installations in accordance with manufacturers' specifications.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1140.4.1 Explain how to overcome site conditions and obstacles that affect the layout of materials and accessories.
- Furniture
 - Appliances
 - Temperature
 - Access
 - Radiators and heating vents
- S1140.4.2 Develop layout schemes for specified materials and establish material and labour components for a job.
- Job Site Access
 - Material Delivery
 - Material Storage
 - Material Layout Schemes
- S1140.4.3 Perform measuring, scaling, and sketching procedures for an assigned layout plan.
- Determine starting point.
 - Use bench marks
 - Use layout tools

Number: S1140.5
Title: Interpret Construction Drawings
 Duration: Total Hours: 3 Theory: 3 Practical: 0
 Cross Reference to Training Standard: U0854.02, U0855.01

General Learning Outcomes

Interpret construction drawings in accordance with blueprint specifications for related installation tasks.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1140.5.1 Access and read construction drawings.

- Floor plans
- Elevations
- Details
- Room schedules

S1140.5.2 Interpret construction drawings for specific installations of Terrazzo, Tile and Natural Stone.

- Dimension lines
- Arrowheads
- Hidden lines
- Area identification
- Abbreviations
- Symbols

Evaluation Structure				
Theory Testing	Practical Application Testing	Projects	Notebook & organizational Skills	Final Assessment
10%	60%	10%	5%	15%

Number:	S1141		
Title:	Construction Techniques And Procedures II		
Duration:	Total Hours: 60	Theory: 10	Practical: 50
Prerequisites:	None		
Content:	S1141 .1 Construction Techniques Planning and Preparation S1141.2 Substrate Preparation		

Evaluation & Testing:

- Assignments related to theory and appropriate application skills
- Minimum of one mid-term test during the term
- Final exam at end of term
- Periodic quizzes

Instructional and Delivery Strategies:

- Lecture and assignment work.

Reference Materials:

Product information as supplied by the manufacturer:

- General installation procedures
- Tool adjustments
- Warranty requirements
- Required installation material
- Conditions for installation

Number: S1141.1
Title: **Construction Techniques Planning And Preparation**
Duration: Total Hours: 8 Theory: 8 Practical: 0
Cross Reference to Training Standard: U0851.01, U854.02, U0855.01 to U0855.04

General Learning Outcomes

Perform planning and preparation for construction techniques of terrazzo, tile and natural stone installations in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1141.1.1 Outline worksite organization practices.
- Safe storage of materials, tools and equipment.
 - Weight distribution.
 - Theft prevention.
 - Protection from other adverse conditions.
- S1141.1.2 Describe various forms of oral and written reports for:
- Safe storage of materials, tools and equipment.
 - Location
 - Strength of shelves
 - Climate
 - Weight distribution.
 - Capacity of storage units
 - Balance of load
 - Material check lists
 - Quantity
 - Quality
 - Job progress
 - Timelines
 - Completion deadlines
 - Discrepancies from plan to site conditions
 - Variations from plan
 - Deterioration of substrate

- Shortage and losses
 - Material theft
 - Breakage
 - Poor quality control

- Equipment and tool break-downs
 - Defective equipment and tools
 - Equipment maintenance issues
 - Abuse of equipment and tools
 - Improper storage

S1141.1.3 Access and identify regulations pertaining to construction techniques and procedures

- Industry regulations
- Government regulations

Number: S1141.2
Title: **Substrate Preparation**
Duration: Total Hours: 52 Theory: 2 Practical: 50
Cross Reference to Training Standard: U0856.01 to U0856.13

General Learning Outcomes

Perform substrate preparation for terrazzo, tile, and natural stone installations in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1141.2.1 Perform visual inspection of to determine substrate condition.
- lumps
 - Depressions
 - Fractures
 - Soiling
 - Contamination
 - Obstructions
 - Structural deficiencies
 - Level
 - Square
 - Uniformity
 - Physically inspect for concave and convex substrate irregularities
- S1141.2.2 Explain the cleaning process for substrates.
- Use of chemicals
 - Sweeping and vacuuming
 - Washing
 - Scrubbing
 - Rough – grinding and scraping

- S1141.2.3 Perform the cleaning process for substrates.
- Using chemicals
 - Using brooms, wire brushes, scrapers, vacuums (wet & dry)
 - Washing using squeegee/mops, wiping cloths, pails & sponges
 - Scrubbing using brushes
 - Grinding using hand or floor grinders
 - Shot blasting
 - Sand blasting
 - Scarifying
- S1141.2.4 Apply WHMIS requirements.
- Using rubber gloves
 - Masks
 - Glasses
 - Provide adequate ventilation
 - Provide adequate lighting
- S1141.2.5 Install anti-fracture materials to structural cracks.
- Using trowels, brushes, rollers
 - Prepare crack
 - Apply primer and bonding material
 - Overlap the crack with a rubber or fiberglass membrane or nylon mesh
 - Perform sealing and allow appropriate curing time and conditions
- S1141.2.6 Prepare and patch fractures, holes, surface cracks and unevenness.
- Using cement/mortar (plus latex)
 - Epoxy-based compound
 - Using trowels, straightedges, squeegees and mixing tools and equipment
- S1141.2.7 Install expansion and control joints on concrete or under bed surfaces.
- Using skill saws with masonry blades
 - Snips
 - Hacksaw
 - Caulking guns
 - Wrenches
 - Flat trowels
 - Pointed trowels
- S1141.2.8 Install tape on cementitious board
- Using specified tape
 - Bonding material
 - Provide recommended set and cure time

- Rub and clean

- S1141.2.9 Prepare a solid and sound surface using snips, hammers, trowels, shovels, straight edges, transits and water levels for the following methods.
- Scratch coat method.
 - Wire lath is fastened to the surface and a coat of latex- Portland cement mortar is applied over the lath.
 - Thin-set/direct-bond method
 - Bonding agent such as epoxy, latex, acrylic, various adhesives are applied directly to the surface
 - Floating-floor method
 - Surface is covered if specified with 6mm of sand and or polyethylene film
 - Installation of 2" x 2" (51 mm x 51 mm) wire mesh
 - Installation of under bed of specified thickness
 - Rough surface – 6 mm sand bed applied under the cleavage membrane
 - Steel trowel or fine broom finish omit sand
 - Apply cleavage membranes over concrete substrates
 - Screed and float
 - Bonded mortar bed method
 - Slurry-bond coat and mortar under bed of specified thickness is applied
- S1141.2.10 Explain the installation procedure for water proofing membranes in “wet areas” such as:
- Shower stalls, Whirlpools, Swimming pools
 - Using scissors, trowels, drills and mixing paddles and knives

Evaluation Structure				
Theory Testing	Practical Application Testing	Projects	Notebook & organizational Skills	Final Assessment
10%	60%	10%	5%	15%

Number:	S1142		
Title:	Terrazzo Installation II		
Duration:	Total Hours: 60	Theory: 15	Practical: 45
Prerequisites:	None		
Content:	S1142.1 Install terrazzo base S1142.2 Install specialty terrazzo floors S1142.3 Install terrazzo to stairs, bases and walls		

Evaluation & Testing:

- Assignments related to theory and appropriate application skills
- Minimum of one mid-term test during the term
- Final exam at end of term
- Periodic quizzes

Instructional and Delivery Strategies:

- Lecture and assignment work.

Reference Materials:

Product information as supplied by the manufacturer:

- General installation procedures
- Tool adjustments
- Warranty requirements
- Required installation material
- Conditions for installation

Number: S1142.1
Title: **Install Terrazzo Base**
Duration: Total Hours: 20 Theory: 4 Practical: 16
Cross Reference to Training Standard U0855.01 to U0855.03, U0857.01 to U0857.02

General Learning Outcomes

Perform terrazzo base installations in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1142.1.1 Describe types and composition of terrazzo base materials.

- Portland Cement Terrazzo
 - Bonded Terrazzo
 - Epoxy Bonded Terrazzo
 - Floating Terrazzo
 - Venetian Terrazzo
 - Palladiana Terrazzo
 - Rustic Terrazzo
 - Terrazzo on Vertical Surfaces
 - Polyacrylate modified cement terrazzo
 - Conductive terrazzo
- Precast Terrazzo
 - Portland cement
 - Epoxy resin
 - Stairs
 - Bases
 - Window sills
- Epoxy Resin Thin Set Terrazzo
- Polyacrylate Modified Cement Terrazzo
- Aggregate Chips
 - Grading sizes
 - Recommended standard sizes
 - Chip size for granite, plastic and glass variations from manufacturers and suppliers.
 - Metal chips of non-corrosive and non-rusting material.

- European chips

- Identify standard chip sizes/ passing screen/ retained on bottom screen.
- Standard terrazzo aggregate defined as domestic marble chips 0, 1, 2.
- Specification writer schedule of various sizes, proportions, types and colours of aggregate and gauges, thickness and types of divider stripes for various locations.

S1142.1.2 Perform the preparation procedures for substrate.

- Sweep and clean until dust free
- Fill cracks and holes
- Apply levelling material as required
- Check for structural integrity

S1142.1.3 Perform base installation.

- Sweep and clean until dust free
- Fill cracks and holes
- Install Portland Cement Terrazzo
 - Apply bonded terrazzo
 - Apply epoxy bonded terrazzo
 - Apply floating terrazzo
 - Apply venetian terrazzo
 - Apply palladiana terrazzo
 - Apply rustic terrazzo
 - Apply terrazzo on vertical surfaces
- Install Precast Terrazzo
 - Apply portland cement
 - Apply epoxy resin
 - Apply to stairs
 - Apply to bases
 - Apply to window sills
- Install epoxy resin thin set terrazzo
- Install polyacrylate modified cement terrazzo
- Install aggregate chips
 - Grading sizes
 - Recommended standard sizes
 - Chip size for granite, plastic and glass variations from manufacturers and suppliers.
 - Metal chips of non-corrosive and non-rusting material.
 - European chips

Evaluation Structure				
Theory Testing	Practical Application Testing	Projects	Notebook & organizational Skills	Final Assessment
10%	60%	10%	5%	15%

Number: S1142.2
Title: **Install Specialty Terrazzo**
Duration: Total Hours: 17 Theory: 5 Practical: 12
Cross Reference to Training Standard: U0857.05

General Learning Outcomes

Perform the installation procedures of specialty terrazzo in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1142.2.1 Describe the installation steps for specialty terrazzo products on floors.

- Types
 - Venetian terrazzo (aggregate chips sizes 1-8)
 - Palladiana (fractured slabs of marble or granite)
 - Epoxy terrazzo (seeding into epoxy)
 - Conductive terrazzo (reduce static discharge)
 - Polyacrylate terrazzo (latex mix)
 - Rustic terrazzo (exposed aggregate)
 - Other types of terrazzo
- Installation steps
 - Install Base strips
 - Install Screed mortar bed
 - Install Floor strips
 - Install Cove divider
 - Install Cove base
 - Prepare terrazzo by combining marble or granite chips
 - Install terrazzo material
 - Perform first grind and apply grout
- Perform second grind
- Apply sealer

S1142.2.2 Determine the steps necessary to take in order to adequately test and prepare the sub-floor or wall.

S1142.2.3 Describe the installation of divider strips for terrazzo pattern.

- Fresh mortar under bed for floor installations

- Mortar for walls
- Epoxy-based methods for base or finished slabs.
- Curing process and time requirements

- S1142.2.4 Describe the process to prepare the terrazzo for installation.
- Combine marble or granite chips of specified size and colour with epoxy or cement.
 - Add pigment to cement as required
 - Use electric or manual tools and water as specified.

- S1142.2.5 Perform terrazzo floor installation.
- Broom clean base slab
 - Apply slurry bond coat
 - Place and screed under bed
 - Install divider strips
 - Spread terrazzo mixture level to top of strips
 - Sprinkle topping with dry aggregate
 - Roll topping with heavy roller and remove excess cement and water
 - Hand trowel topping until surface is smooth with no voids or pin holes
 - Allow recommended curing time.

- S1142.2.6 Perform cleanup of a terrazzo installation.
- Remove any installation debris
 - Remove residue
 - Soak floor and apply slurry bond coat as required
 - Prime the floor for as specified for epoxy terrazzo installations

Number: S1142.3
Title: **Install Terrazzo On Stairs, Bases And Walls**
Duration: Total Hours: 23 Theory: 6 Practical: 17
Cross Reference to Training Standard: U0855.01 to U0855.03, U0857.06, U0857.07

General Learning Outcomes

Perform the installation procedures of terrazzo on stairs, base and walls in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1142.3.1 Describe the types and construction features of stairs.

- Boxed or closed stringer
- Open stringer, one side.
- Open stringer, two sides.
- Winders or pie-shaped.
- Circular or elliptical.

S1142.3.2 Describe tools required for installation on stairs, base and walls.

- Flat trowels
- Cove trowels
- Small hand rollers
- Brushes or whisks
- Base grinders
- Sanding discs
- Files
- chisels

- S1142.3.3 Perform installation of terrazzo on stairs, base and walls.
- Install base bead top strip
 - Apply under bed to backing 8mm from finish surface
 - Place and screed under bed mix
 - Install divider strips, cove dividers, slip resistant channels
 - Apply a slurry bond coat (except for resinous and epoxy bonded)
 - Apply a stiff terrazzo mix to risers, treads, curbs, stringers and other vertical substrates
 - Use flat and cove trowel to uniformly compact aggregate to detailed shape
 - Hand trowel until surface is smooth with no voids
 - Wash off excess cement with brush

- S1142.3.4 Install pre-cast terrazzo on steps and risers.
- Confirm step materials with blueprints and specifications
 - Lay out the stairs
 - Even out treads and risers with screed mix on steel stairs
 - Even out treads and risers with Portland cement mortar on cured under bed and concrete stairs
 - Back butter bonding material to back of treads and risers
 - Anchor the risers
 - Set and align stone treads and risers
 - Grout joints and clean
 - Protect area during curing process
 - Allow specified time to cure

- S1142.3.5 Finish terrazzo installation using base grinding machines.
- First grind
 - Grouting with matching coloured cement
 - Grout and perform second grind
 - Apply sealer

Evaluation Structure				
Theory Testing	Practical Application Testing	Projects	Notebook & organizational Skills	Final Assessment
10%	60%	10%	5%	15%

Number:	S1143		
Title:	Tile Installation II		
Duration:	Total Hours: 60	Theory: 17	Practical: 43
Prerequisites:	None		
Content:	S1143.1 Mosaic tile pattern design S1143.2 Tile lay out S1143.3 Tile installation		

Evaluation & Testing:

- Assignments related to theory and appropriate application skills
- Minimum of one mid-term test during the term
- Final exam at end of term
- Periodic quizzes

Instructional and Delivery Strategies:

- Lecture and assignment work.

Reference Materials:

Product information as supplied by the manufacturer:

- General installation procedures
- Tool adjustments
- Warranty requirements
- Required installation material
- Conditions for installation

Number: S1143.1
Title: **Tile Pattern Design**
Duration: Total Hours: 4 Theory: 4 Practical: 0
Cross Reference to Training Standard: U0858.09

General Learning Outcomes

Describe the tile pattern design process in accordance with manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1143.1.2 Describe the types and applications of standard ceramic tiles.

- Types
 - Porcelain
 - Clay
 - Glass
 - Terrazzo
 - Kinker tile
 - Marble
 - Granite
 - Limestone
 - Sandstone
 - Slate
 - Agglomerate
 - Quarry
 - Paver
 - Glazed
- Applications
 - Shower stalls
 - Whirl pools
 - Swimming pools
 - Back splashes
 - Saunas
 - Gutters
 - Columns
 - Ceilings
 - Arches
 - Bathtub/walls

- S1143.1.2 Describe pattern design process.
- Verify Pattern match
 - Determine die lot match
 - Use pattern scribe process
 - Free hand scribe
 - Direct scribe
 - Strip measure

Number: S1143.2
Title: **Tile Layout**
Duration: Total Hours: 19 Theory: 4 Practical: 15
Cross Reference to Training Standard: U0858.04, U0858.05

General Learning Outcomes

Perform the layout procedures for ceramic tile in accordance with manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1143.2.1 Determine layout schemes for ceramic tile installation.
 - Job Site Access
 - Material Delivery
 - Material Storage
 - Material Layout Schemes

- S1143.2.2 Perform measuring, scaling, and sketching procedures for a layout plan.
 - Determine starting point.
 - Using bench marks
 - Using layout tools.

- S1143.2.3 Perform free-hand sketch to assist communication and clarify details of layout plan.

- S1143.2.4 Perform the dry layout installation for ceramic tile pattern.
 - Place tile against base and floor to determine required cuts and angles
 - Place tile according to layout plan

- S1143.2.5 Test and prepare the substrate

Number: S1143.3
Title: **Tile Installation**
Duration: Total Hours: 37 Theory: 9 Practical: 28
Cross Reference to Training Standard: U0851.01, U0854.02, U0855.01 to U0855.04, U0858.01 to U0858.16, U0860.06

General Learning Outcomes

Perform the installation procedures for ceramic tile in accordance with manufacturer's recommendations and specifications and approved industry standards

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1143.3.1 Describe installation methods for ceramic tile.
- Straight running bond
 - Brick joint
 - Haring bone
 - Diamond pattern
 - Basket weave
 - Stack bond
- S1143.3.2 Describe installation materials required for tile.
- Dry- set mortar
 - Latex modified mortar
 - Epoxy mortar
 - Epoxy grout
 - Fast setting mortar
 - Furan resin mortar
 - Organic adhesives
 - Grout
 - Sanded
 - Un-sanded

- S1143.3.3 Describe materials preparation process for tile installation of:
- Floors
 - Walls
 - Ceilings
 - Arches
 - Bath tub/walls
 - Shower stalls
 - Whirl pools
 - Swimming pools
 - Back splash
 - Saunas
 - gutters
- S1143.3.4 Perform cutting and fitting procedures for ceramic tile installation:
- S1143.3.5 Describe the application procedure for thin set and adhesives.
- S1143.3.6 Perform standard ceramic tile installation according to the specified layout plan.
- Apply scratch coat
 - Apply mortar
 - Apply and screed under bed
 - Spread bond coat or adhesive with trowel
 - Install tile
 - Apply grout
 - Allowing recommended curing time.
 - Apply sealer (if specified)
 - Protect new installation throughout curing time frame
- S1143.3.7 Install surface-mounted and recessed accessories.
- Handicapped safety rails
 - Towel bars
 - Soap and shampoo dishes
 - Prefabricated stair nosing
 - Carborundum inserts
 - Tactile surfaces
- S1143.3.8 List the steps required to perform a successful cleanup of a tile installation.
- Remove all cutting debris
 - Remove grout residue
 - Seal the floor for as specified for tile installations
- S1143.3.9 Remove, repair and maintain damaged tile perform recommended waste disposal.

Evaluation Structure				
Theory Testing	Practical Application Testing	Projects	Notebook & organizational Skills	Final Assessment
10%	60%	10%	5%	15%

Number:	S1144		
Title:	Natural Stone Installation II		
Duration:	Total Hours: 75	Theory: 15	Practical: 60
Prerequisites:	None		
Content:	S1144.1 Mechanical Installations S1144.2 Interior Conventional and Stacking Installations S1144.3 Slabs on Floor Installations S1144.4 Counter Top Installations		

Evaluation & Testing:

- Assignments related to theory and appropriate application skills
- Minimum of one mid-term test during the term
- Final exam at end of term
- Periodic quizzes

Instructional and Delivery Strategies:

- Lecture and assignment work.

Reference Materials:

Product information as supplied by the manufacturer:

- General installation procedures
- Tool adjustments
- Warranty requirements
- Required installation material
- Conditions for installation

Number: S1144.1
Title: **Mechanical Installation**
Duration: Total Hours: 19 Theory: 3 Practical: 16
Cross Reference to Training Standard: U0859.01 to U0859.11

General Learning Outcomes

Perform mechanical installations of natural stone materials in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1144.1.1 Describe the hardware used for mechanical installation of natural stone.

- Types
 - Anchoring devices for concrete
 - Inserts
 - Shims
 - Copper wire
 - Stainless steel angles
 - Stainless bolts
 - Expansion anchor
 - Struts
 - Plate
 - Dowel
 - Electrical separator
 - Liner

S1144.1.2 Describe installation procedure for mechanical hardware.

- Drilling holes for inserts and cutting slots using:
 - Carboloy masonry bits
 - Circular saws
 - Hammers and chisels
 - Adjustable clamps
 - Crowbars, rubber mallets, pliers
- Installing inserts in concrete.
 - Angle iron for first course
 - Galvanized or stainless steel struts
 - Expansion shields
 - Screwing into existing structures
 - Resetting insulation as required

- S1144.1.3 Describe how to confirm slab support and joint size meets specifications.
- Compare slab size and weight with engineering specifications, anchor details and shop drawings.
 - Select appropriate support hardware
 - Measure joint size
- S1144.1.4 Perform mechanical installation of natural stone.
- Set up working platforms
 - Scaffolds
 - Swing stages
 - Scissor lifts
 - Inspect slabs
 - Structural integrity
 - Absence of defects
 - Gaps, voids, small cracks
 - Confirm layout
 - Refer to blueprints and specifications
 - Perform trial layout
 - Book-match if specified
 - Locate starting point and datum line
 - Drill holes and cut slots in specified locations
 - Install inserts
 - Confirm independent support for each slab
 - Confirm joint size
 - Install overhangs
 - Using dowelled liners or “J” plates and epoxy
 - Drilling and dowelling the holes
 - Tighten the wall fasteners
 - Cut openings for accessories
 - Electrical outlets
 - Light switches
 - Floor drains
 - Vents
 - Set slabs in place using:
 - Fork lifts
 - Chain hoists
 - Manually
 - Suction cups
 - Lifting clamps
 - Caulk joints
 - Grout and point joints
 - Clean surface

- S1144.1.5 Perform repair of natural stone.
- Gaps
 - Voids
 - Small cracks
 - Chips

Number: S1144.2
Title: **Interior Conventional And Stacking Installation**
Duration: Total Hours: 19 Theory: 3 Practical: 16
Cross Reference to Training Standard: U0860.01 to U0860.07

General Learning Outcomes

Perform the conventional and stacking installation methods of natural stone in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

S1144.2.1 Describe the hardware used for conventional and stacking method of installing natural stone.

- Types
 - Anchoring devices for substrate
 - Inserts
 - Hooks
 - Copper or non ferrous wire
 - Plaster
 - Latex Portland cement
 - Mortar
 - Epoxy
 - Liner

S1144.2.2 Describe installation procedure for hardware.

- Drilling holes for inserts and cutting slots using:
 - carboloy masonry bits
 - circular saws
 - hammers and chisels
 - adjustable clamps
 - crowbars, rubber mallets, pliers
- Installing inserts in concrete.
 - Angle iron for first course
 - Expansion shields
 - Screwing into existing structures
 - Applying cement, mortar and or epoxy

S1144.2.3 Describe how to confirm slab support and joint size meets specifications.

- Compare slab size and weight with engineering specifications
 - Select appropriate support hardware
 - Measure joint size

S1144.2.4 Perform conventional and stacking installation method of natural stone.

- Set up working platforms
 - Scaffolds
 - Swing stages
 - Scissor lifts
- Inspect slabs
 - Structural integrity
 - Absence of defects
 - Gaps, voids, small cracks
- Confirm layout
 - Refer to blueprints and specifications
 - Perform trial layout
 - Book-match if specified
 - Locate starting point
- Drill holes and cut slots in specified locations
- Install inserts
- Apply cement, mortar and or epoxy
- Confirm independent support for each slab
- Confirm joint size
- Install overhangs
 - Using dowelled liners or “J” plates and epoxy
 - Drilling and dowelling the holes
 - Tighten the wall fasteners
- Cut openings for accessories
 - Electrical outlets
 - Light switches
 - Floor drains
 - Vents
- Set slabs in place using:
 - Fork lifts
 - Chain hoists
 - Manually
 - Suction cups
- Caulk joints
- Grout and point joints
- Clean surface

S1144.2.5 Perform specialty installations for:

- Thresholds
- Shower seats and jams
- Window sills

Terrazzo, Tile and Marble Setter

- Mantels
- Door and window jams

S1144.2.6 Perform repair of natural stone.

- Gaps
- Voids
- Small cracks

Number: S1144.3
Title: **Tile Layout**
Duration: Total Hours: 20 Theory: 4 Practical: 16
Cross Reference to Training Standard: U0861.01 to U0861.11

General Learning Outcomes

Perform the installation of slabs on floors in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1144.3.1 Perform installation of slabs on floors.
- Inspect slabs
 - Structural integrity
 - Absence of defects
 - Size and colour uniformity
 - Chips
 - Voids
 - Confirm layout
 - Refer to blueprints and specifications
 - Perform trial layout
 - Book-match if specified
 - Locate starting point
- S1144.3.2 Perform the preparation requirements for installing natural stone on floors.
- Inspect slabs
 - Confirm layouts by referencing blueprints and drawings
 - Re-check materials
 - Clean and sweep until all contaminants are removed
 - Level base as required
- S1144.3.3 Test and prepare the sub-floor.
- Verify sub-floor material requirements
 - Test sub-floor for dimensional stability
 - Insure sub-floor material is stable and well bonded
- S1144.3.4 Describe the dry layout installation for natural stone floor pattern.
- Identify starting point
 - Place slabs to determine cutting and spacing requirements

- Set square lines and main lines
- S1144.3.5 Describe the process to prepare the natural stone for installation.
- Use of electric or manual tools and water as specified.
- S1144.3.6 Perform standard natural stone floor installations.
- Mix and screed under bed
 - Mix and apply bond coat
 - Mix and apply medium bed

 - Perform dry layout of natural stone
 - Perform cutting and fitting
 - Diamond drilling
 - Diamond blade grinding and cutting
 - Pattern matching
 - Colour matching
 - Spread bond coat to underlayment and backside of slab
 - Install stone
 - Apply grout
 - Allow recommended curing time.
- S1144.3.7 Perform cleanup and maintenance of a natural stone floor installation.
- Remove all cutting debris
 - Remove grout residue
 - Seal the floor as specified
 - Remove bond coat residue
 - Waste disposal and removal of any installation debris
 - Application of protective coatings (if required)
- S1144.3.8 Repair natural stone floors.
- S1144.3.9 Perform the removal and maintenance requirements for natural stone and perform recommended waste disposal.

Number: S1144.4
Title: **Counter Top Installation**
Duration: Total Hours: 17 Theory: 5 Practical: 12
Cross Reference to Training Standard: U0862.01 to U0862.09

General Learning Outcomes

Perform the installation procedures for natural stone on counter tops in accordance with government regulations, manufacturer's recommendations and specifications and approved industry standards.

Learning Outcomes

Upon successful completion the apprentice is able to:

- S1144.4.1 Interpret blueprints and specifications for natural stone counter top installations.
- Required materials
 - Bonding materials
 - Digitizer diagrams and notes
 - Shop drawings
 - Templates
- S1144.4.2 Perform visual inspection of counter tops, backsplash, vanity, aprons, and island tops.
- Confirm strength and integrity
 - Absence of defects
 - Review sink and faucet template is accurate
 - Verify overlap of counter top is as specified
 - Verify that grain direction and veining run in same direction
- S1144.4.3 Perform the recommended and safe lifting, carrying and transporting techniques for natural stone counter top installations.
- Identify various slab thickness and relate to lifting and handling
 - Determine the number of persons required to safely lift and install counter top slabs
 - Use of hand straps
 - Use of lifting clamps
 - Use of suction support bars to help prevent breakage
 - Use of motorized lifting devices
 - Securing slabs during delivery transportation

- S1144.4.4 Describe the installation steps for natural stone on counter tops.
- Preparation of substrate
 - Check measurements
 - Verify if mounting surface is square
 - Check if millwork is level
 - Review tolerances of joint widths
 - Assess millwork and wall for irregularities
 - Verify the integrity of slab support
 - Install aprons
 - Cut out accessory openings
 - Install slabs
 - Grout joints
 - Clean and seal the slab as specified
- S1144.4.5 Perform steps to test and prepare the cabinet base.
- S1144.4.6 Describe the dry layout installation for counter tops.
- Required clearances
 - Level and shimming tests
 - Check gables for span requirements
- S1144.4.7 Prepare the natural stone counter top for installation.
- Cut outs for sink and fixtures
 - Diamond bit grinding requirements
- S1144.4.8 Perform standard natural stone counter top installation.
- Install necessary supports and position under mount sinks
 - Perform dry layout of counter top to verify fit and leveling requirements
 - Verify shim requirements
 - Apply adhesive to substrate
 - Install counter top
 - Install shims as required
 - Mix matching colour to seam adhesive and secure seams if required
 - Apply sealant caulking
 - Allowing recommended curing time.
 - Clean and seal counter top as specified
- S1144.4.9 Perform installation of natural stone backsplash.
- Dry-set backsplash to ensure fit
 - Apply adhesive to wall
 - Install backsplash
 - Caulk or epoxy joints

S1144.4.10 Perform cleanup of a natural stone counter top installation.

- Remove all grinding debris
- Remove caulking residue
- Clean back splash and walls as required.

Evaluation Structure				
Theory Testing	Practical Application Testing	Projects	Notebook & organizational Skills	Final Assessment
10%	60%	10%	5%	15%

APPENDIX I

Summary of Equipment Required for Level II

Unit I: Recommended Minimum Tools and Equipment:

- General Tools
 - Crescent shaped knife
 - Concave cutting gouge
 - Cove base adhesive applicator gun & nozzle
 - Divider scribe
 - Universal scribe
 - Hand roller
 - Trowels
 - pointing
 - flat
 - cove
 - Pliers
 - Metal snips
 - Hammer
 - Chisels
 - Sponges
 - Broom
 - Rake
 - Measuring divider
 - Tape
 - Water level
 - Laser level
 - Square
 - Straight edges
 - Box and open end wrench set
 - 3/8" Socket set

Safety equipment per student

1 - Knee pad set

1 - Hard hat

4 - Respirators per class

1 - Safety glasses

1 - Hearing protection

Job site equipment

- 4 ft. level
- box of white rags
- dollies or hand trucks
- moisture test kit
- hammer drill
- vacuum cleaner
- anchorite tools
- pH test kit
- circular saw
- plumb bobs

Unit 2: Recommended Minimum Tools and Equipment:

- Scaling Tools
- Calculators

Unit 3, 4, & 5: Recommended Minimum Tools and Equipment:

- Hand Tools
 - Tile cutter
 - Crescent shaped knife
 - Concave cutting gouge
 - Cove base adhesive applicator gun & nozzle
 - Divider scribe
 - Universal scribe
 - Hand roller
 - Trowels
 - pointing
 - flat
 - cove
 - Pliers
 - Metal snips
 - Hammer
 - Chisels
 - Sponges
 - Broom
 - Rake
 - Measuring divider
 - Tape
 - Water level
 - Laser level

- Square
- Straight edges

- Power Tools and Equipment
 - Hammer drill
 - Skill saw
 - Cement mixer
 - Base floor machine
 - Wet saw

Unit 6: Recommended Minimum Tools and Equipment:

- Power Tools
 - Circular saws
 - Grinders
 - Mixing drums
 - Tub saws
 - Hammer drills
 - Variable speed drill, ceramic and masonry drill bits
 - Wet saw

- Hand Tools
 - Trowels (notched)
 - Claw hammer
 - Rubber mallet
 - Socket set
 - Box and open end wrenches
 - Pliers
 - Snipes
 - Pinch bar
 - Pry bar

Suggested Projects Level II:

1. Terrazzo – Floor Installation
2. Terrazzo – Base and Wall Installation
3. Tile - Floor and Wall Layout Installation
4. Natural Stone - Floor Layout Installation
5. Natural Stone - Counter Top Layout Installation



**Skilled
Trades**
Ontario

**Métiers
spécialisés**
Ontario

skilledtradesontario.ca



Tilesetter